

University and Government Partnership in Morehead Ground System Development for Space Mission Operations

Timothy Pham^[1], Benjamin Malphrus^[2]

^[1]Jet Propulsion Laboratory, California Institute of Technology

^[2]Morehead State University



Outline

- How partnership is formed
- Background information
- System architecture
- Operational concept
- System performance
- System validation incrementally
- What makes it works



Partnership

- Connection between MSU and DSN
 - via Lunar IceCube/Exploration Mission 1



Lunar IceCube




EM-1




21-m MSU antenna




DSN antennas (34-m/70-m)



NASA Programs




Human Exploration & Operations Mission Directorate



EM-1

EXPLORATION MISSION-1


The first uncrewed, integrated flight test of NASA's Orion spacecraft and Space Launch System rocket, launching from a modernized Kennedy spaceport



Total distance traveled: 1.3 million miles – Mission duration: 25.5 days – Re-entry speed: 24,500 mph (Mach 32) – 13 CubeSats deployed

https://en.wikipedia.org/wiki/Exploration_Mission-1#/media/File:EM1-Mission-Map_Update.jpg

Lunar IceCube



Morehead State University and Goddard are partnering to create the Lunar IceCube mission shown in this artist's rendition.
Credits: Morehead State University




The Busek Company is developing Lunar IceCube's low-thrust electric propulsion system, the RF Ion BIT-3 thruster.
Credits: Busek Company

<https://www.nasa.gov/feature/goddard/lunar-icecube-to-take-on-big-mission-from-small-package>

Background on MSU Capabilities

The Morehead State University Ground Station


- Relatively quiet RFI environment in eastern Kentucky
- 21-m ground station operational since 2006
 - Few in the US large enough for deep space tracking
 - Built under university funding
- Experienced RF and telecom engineers and scientists
- Experienced staff/students in mission operations
 - LRO, ISEE-3, Planet Lab, KySpace, ASTERIA



21 Meter System at Morehead

- Specifications by MSU faculty with NASA assistance
- Dual Purpose Instrument
 - Ground Station for Smallsats
 - Radio Telescope for Astronomy Research
- Funded \$3.4 M -a variety of sources- Morehead State, Federal and State Funds, KSTC, NASA
- Built and Installed by VertexRSI (General Dynamics)
- Feeds Designed and built by VertexRSI, APL, and MSU


Space Projects Create Opportunities for Students



- Undergraduate Research Experiences
- Instrumentation Experience
- Engineering Design
- Observational Astrophysics Research
- Ground Ops (TT&C)
- Project Management Experience
- Systems-level Engineering Experience




Exploring spacecraft throughout Solar System



Deep Space Communications Challenges


- Deep space - Interplanetary communications
 - Extended to the edge of Solar System
 - Voyager spacecraft ~130 AU
- Difference between deep space and LEO communications
 - LEO: ~1000 km
 - Deep space: ~400,000 km (0.003 AU) – 130 AU




Distance	Power reduction
Moon	1.5E+05
Larange points	2.3E+06
Mars	2.3E+10
Jupiter	6.1E+11
Saturn	2.0E+12
Pluto	2.0E+13
Heliosphere	3.3E+14

NASA Deep Space Network

- Provide global coverage at 3 sites around the globe
 - One 70m and three-four 34m antennas at each site
- Support missions from HEO to edge of solar system
- Optimize high performance for deep space communications
 - Compared to typical 10m commercial tracking station
 - Lower noise (3x-6x)
 - Higher gain (10x – 50x)



NASA Deep Space Network




<https://eyes.nasa.gov/dsn/dsn.html>



Jet Propulsion Laboratory
California Institute of Technology

Copyright 2019 California Institute of Technology and Morehead State University.
Government sponsorship acknowledged

NASA Deep Space Network Architecture






Transition from LEO to Lunar Orbit

- Distance: 1000km >> 400,000 km
 - Signal power reduction proportional to distance squared
- Require better link performance
 - Higher frequency: UHF (400 MHz) >> X-band (8 GHz)
 - Lower system noise temperature: 300K >> 100K
 - Higher perform FEC: RS >> Turbo




Implementation Objectives

- Upgrade MSU 21-m antenna to support Lunar IceCube and other EM-1 Cubesats
 - X-band operations
 - Deep space and near Earth
 - Full TTC functions
 - 3 kW power amplifier
 - Deep space specialization
 - Highly efficient FEC (e.g., turbo code, LDPC)
 - Pseudo-noise/sequential ranging
 - Interoperability with DSN and CCSDS compliant




System Attributes

- Minimize implementation cost
 - Leverage on DSN-developed equipment
 - Specialized deep space signal processing for telemetry decoding and ranging
 - Adapt the already-built equipment to only necessary functions
 - Implement the rest with COTS equipment
 - New and surplus components
- Adopt common user interfaces
 - Data delivery at JPL, as with other DSN antennas
- Create opportunity for student-developed projects
 - Station monitor & control
 - System Integration and testing
 - Equipment operations



**X-band Feed
and LNA**




**DSN
Equipment**



**Hydrogen
MASER**

System Architecture



Operation Concept

*Few weeks
before track*

- Antenna scheduling via DSN
 - Transition to operational multi-mission support
 - Schedule conflict resolution

*Few days
before track*

- Prediction data generation by DSN
 - Data retrieved by MSU




*Real-time
during track*

- Data delivery via DSN interface points
 - Command, telemetry, radiometric data
 - WAN Connection to JPL via NASA mission backbone
 - IT security clearance by NASA

*Real-time &
Post track*

- System monitor control and diagnostics
 - Locally controlled and archived
 - Voice network communications with MOS team




System Performance

Performance Measure	Pre-Upgrade	Post-Upgrade
X-Band Frequency Range	7.0 – 7.8 GHz	7.0 – 8.5 GHz
LNA Temperature	70 K	< 20 K
System Noise Temperature	215 K	<100 K
Antenna Gain	62 dBi (@7.7 GHz)	62.7 dBi (@8.4 GHz)
System Noise Spectral Density	-175 dBm/Hz	<-178 dBm/Hz
G/T at 5° Elevation	37.5 dB/K	40.4 dB/K
Time Standard	GPS (40 ns)	Hydrogen maser (1 ns/day)
EIRP	N/A	93.7 dBW
HPBW	0.124 deg	0.115 deg
CCSDS Compliance	N/A	Yes
Forward Error Coding	Reed Solomon/Convolutional	Reed Solomon/Convolutional, Turbo, Low Density Parity Check
Radiometric	Angle, Doppler	Angle, Doppler, Ranging

System Validation, using Internal Test Signal

First Deployment (9/2017)


- Installed DSN equipment
- Conducted loopback tests between uplink and downlink equipment
 - Validated key TTC processing



System Validation, using Internal Test Signal with E2E flow

First Deployment (9/2017)


- Installed DSN equipment
- Conducted loopback tests between uplink and downlink equipment
 - Validated key TTC processing



System Validation, with spacecraft

Second Deployment (5/2018)

- Additionally installed antenna feed, LNA, RF/IF downconversion
- Conducted testing with spacecraft downlink
 - MarCO, Osiris Rex, Maven, Hayabusa2



Shadow Tracking Spacecraft



Currently in progress

- Expected 10-dB G/T difference between DSN and MSU antennas
 - Antenna Gain: MSU (21m) = 0.4* DSN (34m)
 - System Noise Temperature: MSU(100K) = 4*DSN(25K)
- Shadow DSN tracking of missions with sufficient SNR (>10 dB link margin)
 - Hayabusa2, Osiris and Maven




Results with Hayabusa2

- Expected signal strong enough for carrier, subcarrier and symbol locks
 - Not strong enough for telemetry decoded
- Observed 11.3 dB difference between MSU and DSN antennas, based on carrier SNR and symbol SNR
 - Within bounds of 10 dB expectation





Results with Osiris

- Expected signal strong enough for carrier, subcarrier and symbol locks
 - Insufficient bit SNR (E_b/N_0) for telemetry frame decoding
- Observed
 - Achieved carrier lock, but not subcarrier nor symbol locks
 - 10.3 dB difference between MSU and DSN antennas
 - Consistent with expectation





Results with MAVEN

- Expected signal strong enough for carrier, subcarrier and symbol locks and telemetry decoded
- Observed
 - Carrier lock - 11.0 dB difference between MSU and DSN antennas
 - Subcarrier lock – Not achieved
 - Symbol lock – 17 dB difference, due to lack of subcarrier lock
 - Telemetry decode – Not achieved, due to lack of subcarrier lock



Recent results with Osiris & Stereo

- Success!!!
 - Fully decoded telemetry data



What makes it works

- AES programmatic support
- Staff & students expertise
 - Previous Cubesat operations
 - Core engineering staff with RF experiences
 - Small focused team
- Ownership of system
 - Shared responsibilities
- Available funding support

